TENDER DOCUMENT

DEVELOPMENT OF STRATEGICALLY LOCATED WATERPAN IN THE LAIKIPIA LANDSCAPE

LAIKIPIA CONSERVANCIES ASSOCIATION

TENDER NO: LCA/HWC/WATERPAN/2026/826

SCOPE: ESTIMATED TOTAL CAPACITY OF 20,000 M^3

Introduction

The Laikipia Conservancies Association, hereinafter referred to as the Client or Project Manager, intends to invite Contractors to tender for the proposed development of strategically located water pans in priority areas within the Laikipia landscapes.

The proposed works will comprise excavating, shaping, and lining water pans at identified sites, with an estimated combined storage capacity of approximately 20,000 cubic meters (m^3), together with related structures, to redistribute water and alleviate water stress that contributes to human-wildlife conflict.

The project is funded by the Global Environment Facility (GEF) as the prime donor and implemented by Conservation International (CI) as the GEF Implementing Agency, in partnership with the Government of Kenya through the Ministry of Tourism and Wildlife, the State Department for Wildlife, the Kenya Wildlife Conservancy Association (KWCA), the Laikipia Conservancies Association (LCA), and other conservation partners.

Prepared and Issued By

Laikipia Conservancies Association

P.O. Box 287-10400, Nanyuki, Laikipia County, Kenya

Email for Submissions and Enquiries: procurement@laikipiaconservancies.org. | Phone: +254 716 977073

Tender Reference No.: LCA/HWC/WATERPAN/2026/826

Date of Issue: 30th October 2026

Submission Deadline: 15th November 2026, 4:00pm

Table of Contents

PART A: TECHNICAL REQUIREMENTS

SECTION I: Invitation to Tender

SECTION II: Instructions to Tenderers

SECTION III: Tender Evaluation Criteria

- Stage 1: Preliminary Evaluation
- Stage 2: Technical Evaluation
- Stage 3: Financial Evaluation
- Stage 4: Due Diligence

PART B: FINANCIAL (BILL OF QUANTITIES)

Bill of Quantities — Water Pan

Site Schedule and Summary

Grand Summary

SECTION I: Invitation to Tender

The Laikipia Conservancies Association invites electronic proposals, submitted by email only, from qualified, experienced, and duly registered contractors for the development of strategically located water pans in priority areas within the Laikipia landscapes, with an estimated combined storage capacity of approximately 20,000 cubic meters (m^3).

The initiative forms part of Laikipia Conservancies Association's ongoing human-wildlife coexistence programme, aimed at redistributing water availability across the landscape and alleviating the water stress that drives wildlife and livestock into shared, and often conflict-prone, water sources.

Interested and eligible bidders are requested to submit both Technical and Financial Proposals in accordance with the requirements set out in this document.

Background and Rationale

Seasonal water scarcity is a major driver of human-wildlife conflict in the Laikipia landscapes. During dry periods, wildlife and livestock converge on the same limited water points, increasing encounter rates between people, livestock, and predators or other wildlife, and heightening competition over a scarce resource.

Strategically located water pans, distributed away from settlement areas and existing conflict hotspots, help redistribute water across the landscape, reduce the distances livestock and wildlife must travel to drink, and lower the frequency of conflict-triggering encounters. Laikipia Conservancies Association, working with its member conservancies, partner organisations, and county governments, seeks to develop such pans at identified priority sites.

The project is funded by the Global Environment Facility (GEF) as the prime donor and implemented by Conservation International (CI) as the GEF Implementing Agency, in partnership with the Government of Kenya through the Ministry of Tourism and Wildlife, the State Department for Wildlife, the Kenya Wildlife Conservancy Association (KWCA), the Laikipia Conservancies Association (LCA), and other conservation partners.

Objectives of the Assignment

- Develop strategically located water pans, with an estimated combined storage capacity of approximately 20,000 m^3, at priority sites within the Laikipia landscape.
- Redistribute water availability across the landscape to alleviate water stress that contributes to human-wildlife conflict.
- Reduce competition and conflict-prone encounters between wildlife, livestock, and communities at shared water sources.
- Improve dry-season water security for both wildlife and community livestock in identified priority areas.
- Ensure all pans are constructed to Laikipia Conservancies Association's technical specifications for water retention, structural stability, and long-term functionality.

Scope of Works

The Contractor shall be responsible for the full development cycle of each water pan, including but not limited to:

- Site verification and confirmation of priority locations in liaison with Laikipia Conservancies Association, county government counterparts, and respective conservancy/community focal points.
- Topographical assessment and setting out of each pan to the approved design capacity and dimensions.
- Bulk excavation and shaping of the pan basin to achieve the design storage capacity.
- Construction of an inlet/silt trap structure to manage sediment inflow.
- Construction of a spillway/overflow structure to safely manage excess water during high-inflow periods.

- Compaction and, where required by soil conditions, lining of the pan basin (clay core or geomembrane liner) to minimise seepage losses.
- Construction of livestock/wildlife access ramps with gentle gradients to allow safe watering access and reduce bank erosion.
- Perimeter fencing and signage at each site, where specified by Laikipia Conservancies Association.
- Reinstatement of any disturbed ground surrounding each pan and site clean-up on completion.
- Handover of each completed pan with sign-off by Laikipia Conservancies Association and the respective conservancy/community representative.
- Submission of as-built records, survey data confirming achieved storage capacity, photographic documentation (before, during, after), and a completion report per site.

Detailed bill of quantities standard for a water pan cross-section, and material specifications shall be provided as an annex to this tender or issued at a mandatory pre-bid briefing.

Site Schedule

The works shall be carried out at priority sites within the Laikipia landscape. Laikipia Conservancies Association shall confirm the site, individual design capacities, and their combined total (approximately 20,000 m³) prior to contract commencement. Indicative rows are provided below for bidder reference.

Site No.	Location / Community	Landscape (Laikipia	Conservancy / Ward	Est. Capacity (m³)
1				
	TOTAL ESTIMATED CAPACITY (m³)			

Duration of Assignment

The assignment shall be completed within 12 weeks from the date of contract signing and issuance of the notice to commence. A detailed work plan/Gantt chart showing sequencing on the site in Laikipia landscape, shall be submitted as part of the Technical Proposal.

Defects Liability and Handover

A mandatory three (3)-month Defects Liability Period will apply from the date of provisional handover, during which a 5% financial retention will be withheld to guarantee the prompt rectification of any structural, mechanical, or workmanship defects before final sign-off.

The retention shall be released once all notified defects have been rectified to the satisfaction of Laikipia Conservancies Association and final sign-off has been issued.

Environmental and Regulatory Compliance

- Laikipia Conservancies Association shall be responsible for obtaining any NEMA Environmental Impact Assessment (EIA) licence or approval required prior to commencement of works at each site; the Contractor shall not commence physical works at any site until such approval has been confirmed in writing by the Project Manager.
- The Contractor shall comply with all conditions attached to the NEMA EIA licence/approval throughout execution of the Works.
- Any Water Resources Authority (WRA) permit or authorisation required for water abstraction/storage works shall be obtained by Laikipia Conservancies Association prior to commencement; the Contractor shall comply with all conditions attached to such permit during execution of the Works.

Eligibility Criteria

- Registered legal entity (company, partnership, or firm) in good standing, with a valid business registration/incorporation certificate.
- Valid KRA PIN and Tax Compliance Certificate.
- Demonstrated experience in earthworks, water pan/dam construction, or similar water infrastructure works, with at least two (2) verifiable references/completion certificates from similar assignments in the last 5 years.
- Evidence of NCA registration (or equivalent works category, including civil/earthworks) with a valid annual practising licence.
- Ownership or verified access to heavy earthmoving equipment (excavators, bulldozers, compactors) sufficient for works of this scale.
- Adequate technical personnel and logistical capacity to work concurrently or sequentially across multiple, often remote, sites spanning two landscapes.
- No conflict of interest with Laikipia Conservancies Association, its staff, or governing board.
- Willingness to engage and, where possible, employ local labour from host communities.
- Not currently blacklisted or debarred from public procurement, and no contract terminated for non-performance in the preceding two (2) years.

Statement of Financial Capacity

In place of a bank guarantee, tenders must be accompanied by a completed Statement of Financial Capacity (Section VI), supported by the bidder's bank details and either a letter of reference from their bank or a voided/blank cheque, together with a brief declaration of the bidder's financial capacity to undertake a contract of this value. This information will be considered as part of Preliminary and Technical Evaluation.

Bank information submitted in support of this Statement will be treated as confidential by Laikipia Conservancies Association, used solely for the purposes of evaluation, verification, and contract payment, and handled in accordance with the Data Protection Act, 2019.

Technical Proposal Requirements

Bidders shall submit a Technical Proposal comprising:

- Company profile and evidence of registration/compliance documents.
- Relevant experience and references for similar earthworks/water infrastructure projects.
- Proposed methodology and approach to pan excavation, lining, and site sequencing.
- Equipment list and evidence of ownership/access (logbooks, lease agreements, or equivalent).
- Work plan / Gantt chart covering all sites in both landscapes.
- Key personnel CVs, including any hydrology/water engineering expertise.
- Health, safety, and environmental management approach, including erosion and sediment control measures.
- Community engagement and local labour approach.
- Evidence of a valid contractor's all-risk / public liability insurance policy, or a written undertaking to procure such insurance prior to commencement of works.
- Completed Qualification Information and Confidential Business Questionnaire (Section VI).

Financial Proposal Requirements

Bidders shall submit a Financial Proposal using Laikipia Conservancies Association's standard Bill of Quantities (BQ) format (see Part B), providing a unit-cost and total-cost breakdown per pan and an aggregate total for the full scope of works. All prices should be quoted in Kenya Shillings (KES), inclusive of all applicable taxes, and remain valid for a minimum of 90 days from the submission deadline.

Confidentiality and Data Protection

All information relating to this tender, including the tender documents, site information, technical and financial proposals, and any data, reports or records arising from the assignment, shall be treated as confidential. Tenderers and the successful Contractor shall not disclose such information to any third party, or use it for any purpose other than preparing a tender or performing the Contract, without the prior written consent of Laikipia Conservancies Association.

Personal data (including staff CVs, referee details, bank details, and community or beneficiary information) shall be collected, processed, stored and shared only as necessary for the purposes of this tender and the Contract, and in accordance with the Kenya Data Protection Act, 2019 and its regulations. Tenderers and the Contractor shall put in place appropriate technical and organisational safeguards against unauthorised access, loss, alteration or disclosure, and shall notify Laikipia Conservancies Association promptly of any suspected data breach.

Laikipia Conservancies Association, Conservation International and the Global Environment Facility may access and process information submitted by tenderers for evaluation, verification, audit and reporting purposes, subject to these safeguards. These obligations continue after the completion or termination of the Contract.

LCA-KWCA-CI Prohibited Practices

LCA-KWCA-Conservation International (CI) requires that all Delivery Partners, tenderers, contractors, consultants and their sub-contractors, employees and agents observe the highest standards of ethics and integrity during the procurement process and in the performance of any resulting contract, and that they do not engage in any Prohibited Practice. For the purposes of this tender, Prohibited Practices include the following:

- **Corrupt practice** – offering, giving, receiving or soliciting, directly or indirectly, anything of value to improperly influence the actions of another party.
- **Fraudulent practice** – any act or omission, including a misrepresentation, that knowingly or recklessly misleads, or attempts to mislead, a party in order to obtain a financial or other benefit or to avoid an obligation.
- **Coercive practice** – impairing or harming, or threatening to impair or harm, directly or indirectly, any party or its property to improperly influence the actions of a party.
- **Collusive practice** – an arrangement between two or more parties designed to achieve an improper purpose, including improperly influencing the actions of another party.
- **Obstructive practice** – deliberately destroying, falsifying, altering or concealing evidence material to an investigation, making false statements to investigators, or threatening or harassing any party to prevent disclosure of matters relevant to an investigation, or acting to impede CI's audit or inspection rights.

A tenderer found to have engaged in a Prohibited Practice will have its tender rejected and, where a contract has been awarded, the contract may be terminated, without prejudice to any other remedy available to Laikipia Conservancies Association or Conservation International, including debarment from future procurement and referral to the relevant authorities. Any suspected Prohibited Practice shall be reported promptly to Laikipia Conservancies Association. The full CI Prohibited Practices document is available at the link below, and prevails over this summary:

https://cdn.sanity.io/media-libraries/mlmEWUxEY7eQ/files/65b9b02e6459e78d9dae38955efb5db18076b7d0.pdf

Code of Conduct and Ethics

Tenderers and the successful Contractor shall conduct themselves ethically and with integrity in all dealings under this tender and any resulting contract.

The full Code of Conduct is herein linked (https://www.conservation.org/about/our-commitment-to-ethics/code-of-conduct). Delivery Partners are expected to review and adhere to the principles outlined in the Code of Conduct.

SECTION II: Instructions to Tenderers

1. General, Eligibility and Cost of Tendering

1.1 Laikipia Conservancies Association, as the Employer, invites tenders for the Works Contract described in this document. The successful tenderer will be expected to complete the Works by the Intended Completion Date specified herein.

1.2 All tenderers shall provide, as part of the Qualification Information, a statement that the tenderer is not associated, directly or indirectly, with any consultant or entity that prepared the design or specifications for this project, or that is proposed as Project Manager for the Contract.

1.3 All tenderers shall provide in the Form of Tender and Qualification Information a preliminary description of the proposed work method and schedule as necessary.

1.4 The tenderer shall bear all costs associated with the preparation and submission of its tender, and Laikipia Conservancies Association will in no case be responsible or liable for those costs.

1.5 Tenderers who have been blacklisted, debarred, or whose contracts with any procuring entity have been terminated for non-performance in the last 2 years prior to the date of tender advertisement are not eligible to participate.

1.6 Laikipia Conservancies Association's employees, board members, committee members, and their relatives (spouse and children) are not eligible to participate in this tender.

2. Tender Documents

2.1 The complete set of tender documents comprises: these Instructions to Tenderers; Form of Tender and Qualification Information; Drawings; Bill of Quantities; and Forms of Securities.

2.2 The tenderer shall examine all instructions, forms, and specifications in the tender documents. Failure to furnish all information required, or submission of a tender not substantially responsive in every respect, will be at the tenderer's risk and may result in rejection.

2.3 Enquiries from prospective tenderers shall be addressed during the pre-bid briefing referenced in Section I.

2.4 Before the deadline for submission of tenders, Laikipia Conservancies Association may modify the tender documents by issuing a written addendum, which shall be communicated in writing or by email to all registered bidders.

3. Preparation of Tenders

3.1 All documents relating to the tender and any correspondence shall be in the English language.

3.2 The tenderer shall fill in rates and prices for all items of Works described in the Bill of Quantities. Items for which no rate or price is entered will not be paid for when executed and shall be deemed covered by other rates and prices in the Bill of Quantities.

3.3 All duties, taxes, and other levies payable by the Contractor under the Contract shall be included in the tender price submitted.

3.4 The unit rates and prices shall be quoted in Kenya Shillings.

3.5 Tenders shall remain valid for a period of fourteen (14) days from the submission deadline. Laikipia Conservancies Association may request an extension of this validity period in writing; a tenderer may refuse such a request without prejudice.

3.6 The tenderer shall furnish, as part of the tender, a completed Statement of Financial Capacity

3.7 Any tender not accompanied by a completed Statement of Financial Capacity and supporting bank documentation shall be rejected.

3.8 The tenderer shall submit only one completed tender document, clearly marked with the tender reference number and tender name.

3.9 The submitted tender shall be typed or written in indelible ink and signed by a person duly authorised to sign on behalf of the tenderer. All pages where alterations or additions have been made shall be initialled.

4. Submission of Tenders

4.1 Proposals must be submitted by email only to procurement@laikipiaconservancies.org. Physical or hand-delivered submissions will NOT be accepted.

4.2 The email subject line must clearly state the tender reference number: LCA/HWC/WATERPAN/2026/826.

4.3 Technical and Financial Proposals, including the completed Bill of Quantities, should be attached as separate, clearly labelled PDF documents.

4.4 Tenders shall be submitted not later than 15th November 2026, 4:00pm. Any tender received after the deadline will not be considered.

4.5 Tenderers may modify or withdraw their tenders by giving written notice before the submission deadline. No tender may be modified after the deadline.

4.6 Tenderers may only offer discounts or otherwise modify the prices of their tenders by submitting a formal tender modification before the deadline.

5. Tender Opening and Evaluation

5.1 Tenders received by the deadline will be opened and logged by Laikipia Conservancies Association's Procurement Committee. Given the electronic submission format, a physical tender-opening event will not be held; a tender opening register/report shall nonetheless be prepared.

5.2 Information relating to examination, clarification, evaluation, and comparison of tenders shall not be disclosed to tenderers or third parties until the award to the successful tenderer has been announced. Any effort by a tenderer to influence Laikipia Conservancies Association's officials or the evaluation process shall result in rejection of its tender.

5.3 Laikipia Conservancies Association may, at its discretion, request written or email clarification of any tender, including breakdowns of unit rates. No change in the price or substance of a tender shall be permitted except to confirm correction of arithmetic errors.

5.4 Prior to detailed evaluation, Laikipia Conservancies Association will determine whether each tender (a) meets the eligibility criteria; (b) has been properly signed; (c) is accompanied by a completed Statement of Financial Capacity and supporting bank documentation; and (d) is substantially responsive to the tender documents.

5.5 A tender that is not substantially responsive will be rejected and may not subsequently be made responsive by correction or withdrawal of the non-conforming deviation.

6. Award of Contract

6.1 Subject to Clause 6.2, the Contract will be awarded to the tenderer whose tender is substantially responsive and has offered the lowest evaluated tender price, provided the tenderer is eligible and qualified in accordance with this document.

6.2 Laikipia Conservancies Association reserves the right to accept or reject any tender, and to cancel the tendering process and reject all tenders at any time prior to award, without incurring liability to affected tenderers or any obligation to state its reasons.

6.3 The successful tenderer will be notified of the award in writing or by email prior to expiration of the tender validity period.

6.4 Failure of the successful tenderer to comply with Clause 6.3 shall constitute grounds for cancellation of the award, and the tenderer may be barred from participating in future tenders issued by Laikipia Conservancies Association for a period of up to two (2) years.

6.5 Tender evaluation shall be carried out within a maximum of 21 calendar days from the closing date of the tender.

7. Corrupt and Fraudulent Practices

7.1 Laikipia Conservancies Association requires that tenderers observe the highest standards of ethics during the procurement process and execution of contracts.

7.2 In addition, tenderers shall comply with the CI Prohibited Practices and the Conservation International Code of Conduct described in Section I of this document.

8. Appeal Period

8.1 Any bidder who wishes to appeal against the outcome of the tender shall do so in writing within three (3) working days of the date of the notification/regret letter, addressed to: The Chairperson, Procurement Committee, Laikipia Conservancies Association, procurement@laikipiaconservancies.org. Letters and emails received after this period shall be treated as null and void.

SECTION III: Tender Evaluation Criteria

After tender opening, tenders will be evaluated in four stages: (1) Preliminary Evaluation, (2) Technical Evaluation, (3) Financial Evaluation, and (4) Due Diligence.

Stage 1: Preliminary Evaluation

Bids will be evaluated based on the criteria below. Bids lacking any of the mandatory documents will be considered non-responsive and eliminated at this stage.

No.	Mandatory Requirement	Marks	Compliant?
1	Copy of Certificate of Incorporation / Registration	1 or 0	
2	Copy of valid KRA Tax Compliance Certificate	1 or 0	
3	Copy of CR12 (or equivalent) generated within the last 12 months	1 or 0	
4	Copy of valid business trading licence	1 or 0	
5	Completed Statement of Financial Capacity, with bank details and a bank reference letter or voided/blank cheque attached	1 or 0	
6	Copies of 2 most recent audited financial statements, signed and dated	1 or 0	
7	Evidence of NCA registration (or equivalent works category) with valid annual practising licence	1 or 0	
8	Commitment to undertake the works across all sites within the proposed schedule	1 or 0	
9	Company profile with details of relevant past experience	1 or 0	
10	All pages sequentially paginated and the document duly signed	1 or 0	

Stage 2: Technical Evaluation

Tenders that pass the Preliminary Evaluation will be scored on the following technical criteria. A bidder must score at least 60% of the total available marks to qualify for Financial Evaluation.

No.	Description of Requirement	Max Score
1	Key personnel: technical team leader and site supervisors — qualifications and years of relevant experience	20 Marks
2	Average annual turnover (last 2 audited financial years) relative to the estimated project cost	15 Marks
3	Proposed methodology and work plan/Gantt chart for sequencing works across all sites	15 Marks
4	Proof of similar completed works within the last 5 years (building construction or rural infrastructure)	20 Marks
5	Equipment and logistical capacity to work across multiple, often remote, sites	15 Marks
6	Health, safety, and environmental management approach	10 Marks
7	Litigation history declaration (sworn affidavit, if any)	5 Marks
	TOTAL	**100 Marks**

Stage 3: Financial Evaluation

Upon completion of Technical Evaluation, a detailed financial evaluation shall follow, comprising three parts:

(a) Determination of Arithmetic Errors — In the event of a discrepancy between the amount in figures and words, the amount in words shall prevail. Where there is a discrepancy between a unit rate and its extended line total, the unit rate as quoted shall prevail unless there is an obvious typographical error.

(b) Comparison of Rates — Items that are significantly under-priced or overpriced may indicate risk of non-delivery or front-loading. Laikipia Conservancies Association may request a detailed cost breakdown for such items before making an award recommendation.

(c) Consistency of Rates — The evaluation committee will compare the consistency of rates for similar items across the Bill of Quantities and note any inconsistencies.

Stage 4: Due Diligence

Laikipia Conservancies Association may subject the top-ranked bidder(s) who pass Technical and Financial Evaluation to a due diligence process, which may include reference checks, site visits to past projects, and verification of submitted documents, prior to final award.

PART B: Financial (Bill of Quantities)

Bill of Quantities — Water Pan

Bidders are required to complete the Bill of Quantities below in full. Rates and amounts should reflect the cost of developing ONE standard water pan to Laikipia Conservancies Association specifications; the Site Schedule and Grand Summary should reflect pricing for the full scope (combined estimated capacity of approximately 20,000 m³). Bidders may attach a separate signed/stamped BQ sheet if more space is required, and should note that unit rates for excavation are typically quoted per cubic meter (CM).

Element 1: Site Preparation and Setting Out

Item	Description	Unit	Qty	Unit Rate (KES)	Amount (KES)	Remarks
1	Site clearance of bush, shrubs, and trees within the works footprint; cart away debris	SM	3,000			
2	Topographical survey and setting out of pan basin, embankment, and spillway to approved design	Item	1			
3	Stripping and stockpiling of topsoil for later reinstatement	CM	300			

Element 2: Bulk Excavation and Basin Shaping

Item	Description	Unit	Qty	Unit Rate (KES)	Amount (KES)	Remarks
1	Bulk excavation of pan basin to design profile and capacity (per m³ excavated)	CM	2,500			
2	Formation and compaction of embankment/bund using suitable excavated material	CM	600			
3	Trimming and shaping of basin slopes and banks to design gradient	SM	1,200			
4	Disposal/spreading of surplus spoil within an agreed distance of the site	CM	400			

Element 3: Lining and Seepage Control

Item	Description	Unit	Qty	Unit Rate (KES)	Amount (KES)	Remarks
1	Supply and compaction of clay core / puddle clay lining to basin (where suitable clay is available on or near site)	SM	1,200			
2	Alternative: supply and installation of geomembrane liner (HDPE or equivalent), including protective geotextile underlay	SM	1,200			
3	Anchor trench for liner edges around basin perimeter	LM	180			

Note: Bidders should price Item 1 (clay lining) OR Item 2 (geomembrane liner) based on the specification confirmed for each site; both are listed for pricing flexibility and should not be double-counted in the subtotal.

Element 4: Inlet, Silt Trap and Spillway Structures

Item	Description	Unit	Qty	Unit Rate (KES)	Amount (KES)	Remarks
1	Construction of inlet channel with silt trap to manage sediment inflow	Item	1			
2	Construction of masonry/reinforced concrete spillway and overflow structure	CM	12			
3	Rip-rap or gabion protection at spillway outlet to prevent scour	CM	15			
4	Livestock/wildlife access ramp(s), gently graded, with erosion-resistant surface	No.	2			

Element 5: Fencing, Signage and Site Reinstatement

Item	Description	Unit	Qty	Unit Rate (KES)	Amount (KES)	Remarks
1	Perimeter fencing around pan (where specified), with designated livestock/wildlife access points	LM	250			
2	Signage — site identification, safety, and usage guidance	No.	2			
3	Mobilisation and demobilisation of earthmoving equipment to site	Item	1			
4	Labour — skilled (plant operators, masons)	Item	1			
5	Labour — unskilled (general site assistance)	Item	1			
6	Topsoil reinstatement and site clean-up on completion	Item	1			
7	Post-construction survey confirming as-built storage capacity	Item	1			
8	Handover documentation and photographic record per site	Item	1			
9	Other (specify)	Item	1			
	Subtotal (per water pan)					
	Contingency (%)					
	VAT / Applicable Taxes					
	TOTAL COST PER WATER PAN (KES)					

Site Schedule and Summary

The unit cost per cubic metre established in the Bill of Quantities above shall be applied to a specific site from LCA guidance, scaled to its individual design capacity, unless site-specific ground conditions are flagged.

Grand Summary — Full Scope of Works

Item	Description	Est. Capacity (m^3)	Total Amount (KES)
1	Subtotal — all sites (from Site Schedule above)		
2	Mobilisation / demobilisation costs (if quoted separately)		
3	Supervision / project management costs (if quoted separately)		
	GRAND TOTAL (KES) — Inclusive of All Taxes		

(Carried to Form of Tender)

Bidder Name: _____

Authorised Signature: _____ Date: _____

Company Stamp/Seal: