TENDER DOCUMENT

DRILLING AND EQUIPPING OF COMMUNITY BOREHOLE WITH SOLAR-POWERED PUMPING SYSTEM

LAIKIPIA CONSERVANCIES ASSOCIATION

TENDER NO: LCA/HWC/BOREHOLE/2026/836

Introduction

The Laikipia Conservancies Association, hereinafter referred to as the Client or Project Manager, intends to invite Contractors to tender for the proposed drilling and equipping of community-run borehole with solar-powered pumping systems in Laikipia .

Proposed works will comprise the drilling, testing, and equipping of the borehole with solar pumping systems, to supply water for domestic and livestock use, thereby reducing community dependency on river systems in areas associated with crocodile and elephant attacks on people.

The project is funded by the Global Environment Facility (GEF) as the prime donor and implemented by Conservation International (CI) as the GEF Implementing Agency, in partnership with the Government of Kenya through the Ministry of Tourism and Wildlife, the State Department for Wildlife, the Kenya Wildlife Conservancy Association (KWCA), the Laikipia Conservancies Association (LCA), and other conservation partners.

Prepared and Issued By

Laikipia Conservancies Association

P.O. Box 287-10400, Nanyuki, Laikipia County, Kenya

Email for Submissions and Enquiries: procurement@laikipiaconservancies.org | Phone: +254 716 977073

Tender Reference No.: LCA/HWC/BOREHOLE/2026/836

Date of Issue: 30th October 2026

Submission Deadline: 15th November 2026, 4:00pm

Table of Contents

PART A: TECHNICAL REQUIREMENTS

SECTION I: Invitation to Tender

SECTION II: Instructions to Tenderers

SECTION III: Tender Evaluation Criteria

- Stage 1: Preliminary Evaluation
- Stage 2: Technical Evaluation
- Stage 3: Financial Evaluation
- Stage 4: Due Diligence

PART B: FINANCIAL (BILL OF QUANTITIES)

Bill of Quantities

Site Schedule and Summary

Grand Summary

SECTION I: Invitation to Tender

The Laikipia Conservancies Association invites electronic proposals, submitted by email only, from qualified, experienced, and duly registered contractors for the drilling, testing, and equipping of one(1) community-run borehole with solar-powered pumping systems in Laikipia landscape.

The initiative forms part of Laikipia Conservancies Association's ongoing human-wildlife coexistence programme, aimed at supplying reliable water for domestic and livestock use at community-managed points away from riverbanks, thereby reducing dependency on river systems in areas associated with crocodile and elephant attacks on people.

Interested and eligible bidders are requested to submit both Technical and Financial Proposals in accordance with the requirements set out in this document.

Background and Rationale

In parts of the Laikipia landscapes, households and livestock keepers rely on rivers for domestic and livestock water needs. These riverside water points are frequently also used by crocodiles and elephants, and encounters at the water's edge, particularly during dry seasons when river access is most necessary, have resulted in fatal and non-fatal attacks on people.

Community-run borehole, equipped with solar-powered pumping systems and located away from riverbanks, provide a safer and more reliable alternative water source, reducing the frequency with which people and livestock need to approach known crocodile and elephant hotspots along rivers. Laikipia Conservancies Association, working with its member conservancies, partner organisations, and county governments, seeks to drill and equip one such borehole at identified priority sites.

The project is funded by the Global Environment Facility (GEF) as the prime donor and implemented by Conservation International (CI) as the GEF Implementing Agency, in partnership with the Government of Kenya through the Ministry of Tourism and Wildlife, the State Department for Wildlife, the Kenya Wildlife Conservancy Association (KWCA), the Laikipia Conservancies Association (LCA), and other conservation partners.

Objectives of the Assignment

- Drill, test, and equip one (1) borehole in Laikipia at site identified as priority alternative to conflict-prone river water points.
- Install solar-powered pumping systems at each borehole to ensure reliable, low-maintenance water supply without reliance on grid power or fuel.
- Supply water for both domestic and livestock use at each site, appropriately configured with separate draw-off points where required.
- Reduce community dependency on river systems in areas associated with crocodile and elephant attacks on people.
- Establish a functional community water management structure (e.g. water user committee) capable of operating and maintaining each borehole after handover.

Scope of Works

The Contractor shall be responsible for the full development cycle of each borehole, including but not limited to:

- Site verification and confirmation of the one (1) priority location in liaison with Laikipia Conservancies Association, county government counterparts, and respective conservancy/community focal points.
- Hydrogeological survey and siting of each borehole to confirm groundwater potential prior to drilling.
- Mobilisation of drilling rig and equipment to each site.
- Drilling of the borehole to the depth required to achieve a reliable and sustainable yield, with full geological logging.

- Supply and installation of casing, screens, and gravel packing as required by the strata encountered.
- Development and test-pumping of the borehole to determine sustainable yield and drawdown, with results submitted to Laikipia Conservancies Association.
- Water quality testing (physical, chemical, and bacteriological) to confirm suitability for domestic and livestock use.
- Supply and installation of a solar-powered submersible pump, solar panel array, mounting structure, and associated controls.
- Construction of an elevated water storage tank, with pipework to a domestic draw-off point (tap stand) and a separate livestock watering trough.
- Construction of a wellhead protection slab and fencing around the borehole and solar installation to prevent contamination, vandalism, and theft.
- Basic training of an identified community water user committee on operation, basic maintenance, and reporting of faults for each borehole.
- Reinstatement of any disturbed ground and site clean-up on completion.
- Handover of each completed borehole with sign-off by Laikipia Conservancies Association and the respective conservancy/community representative.
- Submission of as-built records, drilling and test-pumping logs, water quality test results, photographic documentation (before, during, after), and a completion report per site.

Detailed technical specifications for casing, solar system sizing, and storage/distribution infrastructure shall be provided as an annex to this tender.

Site Schedule

The works shall be carried out at one (1) site in Laikipia each identified as a priority alternative to a conflict-prone river water point. Laikipia Conservancies Association shall confirm the final list of sites prior to contract commencement.

Duration of Assignment

The assignment shall be completed within 15 weeks from the date of contract signing and issuance of the notice to commence. A detailed work plan/Gantt chart showing sequencing one site in Laikipia , shall be submitted as part of the Technical Proposal.

Defects Liability and Handover

A mandatory three (3)-month Defects Liability Period will apply from the date of provisional handover, during which a 5% financial retention will be withheld to guarantee the prompt rectification of any structural, mechanical, or workmanship defects before final sign-off.

The retention shall be released once all notified defects have been rectified to the satisfaction of Laikipia Conservancies Association and final sign-off has been issued.

Environmental and Regulatory Compliance

- Laikipia Conservancies Association and shall be responsible for obtaining any NEMA Environmental Impact Assessment (EIA) licence or approval required prior to commencement of works at each site; the Contractor shall not commence physical works at any site until such approval has been confirmed in writing by the Project Manager.
- The Contractor shall comply with all conditions attached to the NEMA EIA licence/approval throughout execution of the Works.
- Any Water Resources Authority (WRA) permit or authorisation required for water abstraction/storage works shall be obtained by Laikipia Conservancies Association prior to commencement; the Contractor shall comply with all conditions attached to such permit during execution of the Works.

Eligibility Criteria

- Registered legal entity (company, partnership, or firm) in good standing, with a valid business registration/incorporation certificate.
- Valid KRA PIN and Tax Compliance Certificate.
- Valid drilling licence/permit from the Water Resources Authority (WRA) or successor body, and demonstrated experience in borehole drilling, testing, and equipping, with at least two (2) verifiable references/completion certificates from similar assignments in the last 5 years.
- Demonstrated experience in solar-powered water pumping system design, supply, and installation.
- Ownership or verified access to a suitable drilling rig and associated equipment for works of this scale.
- Adequate technical personnel (including a qualified hydrogeologist or driller) and logistical capacity to work across sites in Laikipia
- No conflict of interest with Laikipia Conservancies Association, its staff, or governing board.
- Willingness to engage and, where possible, employ local labour from host communities.
- Not currently blacklisted or debarred from public procurement, and no contract terminated for non-performance in the preceding two (2) years.

Statement of Financial Capacity

Bank information submitted in support of this Statement will be treated as confidential by Laikipia Conservancies Association, used solely for the purposes of evaluation, verification, and contract payment, and handled in accordance with the Data Protection Act, 2019.

Technical Proposal Requirements

Bidders shall submit a Technical Proposal comprising:

- Company profile and evidence of registration/compliance documents, including drilling licence/permit.
- Relevant experience and references for similar borehole drilling and solar pumping projects.
- Proposed methodology and approach to siting, drilling, testing, and equipping each borehole.
- Equipment list (drilling rig, testing equipment) and evidence of ownership/access.
- Work plan / Gantt chart covering site in Laikipia.
- Key personnel CVs, including the proposed hydrogeologist/driller and solar systems technician.
- Health, safety, and environmental management approach.
- Proposed approach to establishing and training the community water user committee at each site.

Financial Proposal Requirements

Bidders shall submit a Financial Proposal using Laikipia Conservancies Association's standard Bill of Quantities (BQ) format (see Part B), providing a unit-cost and total-cost breakdown per borehole and an aggregate total for the full scope of works. All prices should be quoted in Kenya Shillings (KES), inclusive of all applicable taxes.

Confidentiality and Data Protection

All information relating to this tender, including the tender documents, site information, technical and financial proposals, and any data, reports or records arising from the assignment, shall be treated as confidential. Tenderers and the successful Contractor shall not disclose such information to any third party, or use it for any purpose other than preparing a tender or performing the Contract, without the prior written consent of Laikipia Conservancies Association.

Personal data (including staff CVs, referee details, bank details, and community or beneficiary information) shall be collected, processed, stored and shared only as necessary for the purposes of this tender and the Contract, and in accordance with the Kenya Data Protection Act, 2019 and its regulations. Tenderers and the Contractor shall put in

place appropriate technical and organisational safeguards against unauthorised access, loss, alteration or disclosure, and shall notify Laikipia Conservancies Association promptly of any suspected data breach.

Laikipia Conservancies Association, Conservation International and the Global Environment Facility may access and process information submitted by tenderers for evaluation, verification, audit and reporting purposes, subject to these safeguards. These obligations continue after the completion or termination of the Contract.

CI Prohibited Practices

Conservation International (CI) requires that all Delivery Partners, tenderers, contractors, consultants and their sub-contractors, employees and agents observe the highest standards of ethics and integrity during the procurement process and in the performance of any resulting contract, and that they do not engage in any Prohibited Practice. For the purposes of this tender, Prohibited Practices include the following:

- **Corrupt practice** – offering, giving, receiving or soliciting, directly or indirectly, anything of value to improperly influence the actions of another party.
- **Fraudulent practice** – any act or omission, including a misrepresentation, that knowingly or recklessly misleads, or attempts to mislead, a party in order to obtain a financial or other benefit or to avoid an obligation.
- **Coercive practice** – impairing or harming, or threatening to impair or harm, directly or indirectly, any party or its property to improperly influence the actions of a party.
- **Collusive practice** – an arrangement between two or more parties designed to achieve an improper purpose, including improperly influencing the actions of another party.
- **Obstructive practice** – deliberately destroying, falsifying, altering or concealing evidence material to an investigation, making false statements to investigators, or threatening or harassing any party to prevent disclosure of matters relevant to an investigation, or acting to impede CI's audit or inspection rights.

A tenderer found to have engaged in a Prohibited Practice will have its tender rejected and, where a contract has been awarded, the contract may be terminated, without prejudice to any other remedy available to Laikipia Conservancies Association or Conservation International, including debarment from future procurement and referral to the relevant authorities. Any suspected Prohibited Practice shall be reported promptly to Laikipia Conservancies Association. The full CI Prohibited Practices document is available at the link below, and prevails over this summary:

https://cdn.sanity.io/media-libraries/mlmEWUxEY7eQ/files/65b9b02e6459e78d9dae38955efb5db18076b7d0.pdf

Code of Conduct and Ethics

Tenderers and the successful Contractor shall conduct themselves ethically and with integrity in all dealings under this tender and any resulting contract.

The full Code of Conduct is herein linked (https://www.conservation.org/about/our-commitment-to-ethics/code-of-conduct). Delivery Partners are expected to review and adhere to the principles outlined in the Code of Conduct.

SECTION II: Instructions to Tenderers

1. General, Eligibility and Cost of Tendering

1.1 Laikipia Conservancies Association, as the Employer, invites tenders for the Works Contract described in this document. The successful tenderer will be expected to complete the Works by the Intended Completion Date specified herein.

1.2 All tenderers shall provide, as part of the Qualification Information, a statement that the tenderer is not associated, directly or indirectly, with any consultant or entity that prepared the design or specifications for this project, or that is proposed as Project Manager for the Contract.

1.3 All tenderers shall provide in the Form of Tender and Qualification Information a preliminary description of the proposed work method and schedule as necessary.

1.4 The tenderer shall bear all costs associated with the preparation and submission of its tender, and Laikipia Conservancies Association will in no case be responsible or liable for those costs.

1.5 Tenderers who have been blacklisted, debarred, or whose contracts with any procuring entity have been terminated for non-performance in the last 2 years prior to the date of tender advertisement are not eligible to participate.

1.6 Laikipia Conservancies Association's employees, board members, committee members, and their relatives (spouse and children) are not eligible to participate in this tender.

2. Tender Documents

2.1 The complete set of tender documents comprises: these Instructions to Tenderers; Form of Tender and Qualification evaluation Information; Drawings; Bill of Quantities.

2.2 The tenderer shall examine all instructions, forms, and specifications in the tender documents. Failure to furnish all information required, or submission of a tender not substantially responsive in every respect, will be at the tenderer's risk and may result in rejection.

2.3 Enquiries from prospective tenderers will be addressed via the email *procurement@laikipiaconservancies.org.*

2.4 Before the deadline for submission of tenders, Laikipia Conservancies Association may modify the tender documents by issuing a written addendum, which shall be communicated in writing or by email to all registered bidders.

3. Preparation of Tenders

3.1 All documents relating to the tender and any correspondence shall be in the English language.

3.2 The tenderer shall fill in rates and prices for all items of Works described in the Bill of Quantities. Items for which no rate or price is entered will not be paid for when executed and shall be deemed covered by other rates and prices in the Bill of Quantities.

3.3 All duties, taxes, and other levies payable by the Contractor under the Contract shall be included in the tender price submitted.

3.4 The unit rates and prices shall be quoted in Kenya Shillings.

3.5 Tenders shall remain valid for a period of fourteen (14) days from the submission deadline. Laikipia Conservancies Association may request an extension of this validity period in writing; a tenderer may refuse such a request without prejudice.

3.6 The tenderer shall furnish, as part of the tender, a completed Statement of Financial Capacity.

3.7 The tenderer shall submit only one completed tender document, clearly marked with the tender reference number and tender name.

3.8 The submitted tender shall be typed or written in indelible ink and signed by a person duly authorised to sign on behalf of the tenderer. All pages where alterations or additions have been made shall be initialled.

4. Submission of Tenders

4.1 Proposals must be submitted by email only to procurement@laikipiaconservancies.org. Physical or hand-delivered submissions will NOT be accepted.

4.2 The email subject line must clearly state the tender reference number: LCA/HWC/BOREHOLES/2026/836.

4.3 Technical and Financial Proposals, including the completed Bill of Quantities, should be attached as separate, clearly labelled PDF documents.

4.4 Tenders shall be submitted not later than 15th November 2026, 4:00pm. Any tender received after the deadline will not be considered.

4.5 Tenderers may modify or withdraw their tenders by giving written notice before the submission deadline. No tender may be modified after the deadline.

4.6 Tenderers may only offer discounts or otherwise modify the prices of their tenders by submitting a formal tender modification before the deadline.

5. Tender Opening and Evaluation

5.1 Tenders received by the deadline will be opened and logged by Laikipia Conservancies Association's Procurement Committee. Given the electronic submission format, a physical tender-opening event will not be held; a tender opening register/report shall nonetheless be prepared.

5.2 Information relating to examination, clarification, evaluation, and comparison of tenders shall not be disclosed to tenderers or third parties until the award to the successful tenderer has been announced. Any effort by a tenderer to influence Laikipia Conservancies Association's officials or the evaluation process shall result in rejection of its tender.

5.3 Laikipia Conservancies Association may, at its discretion, request written or email clarification of any tender, including breakdowns of unit rates. No change in the price or substance of a tender shall be permitted except to confirm correction of arithmetic errors.

5.4 Prior to detailed evaluation, Laikipia Conservancies Association will determine whether each tender (a) meets the eligibility criteria; (b) has been properly signed; (c) is accompanied by a completed Statement of Financial Capacity and supporting bank documentation; and (d) is substantially responsive to the tender documents.

5.5 A tender that is not substantially responsive will be rejected and may not subsequently be made responsive by correction or withdrawal of the non-conforming deviation.

6. Award of Contract

6.1 Subject to Clause 6.2, the Contract will be awarded to the tenderer whose tender is substantially responsive and has offered the lowest evaluated tender price, provided the tenderer is eligible and qualified in accordance with this document.

6.2 Laikipia Conservancies Association reserves the right to accept or reject any tender, and to cancel the tendering process and reject all tenders at any time prior to award, without incurring liability to affected tenderers or any obligation to state its reasons.

6.3 The successful tenderer will be notified of the award in writing or by email prior to expiration of the tender validity period.

6.4 Failure of the successful tenderer to comply with Clause 6.3 shall constitute grounds for cancellation of the award, and the tenderer may be barred from participating in future tenders issued by Laikipia Conservancies Association for a period of up to two (2) years.

6.5 Tender evaluation shall be carried out within a maximum of 21 calendar days from the closing date of the tender.

8. Appeal Period

8.1 Any bidder who wishes to appeal against the outcome of the tender shall do so in writing within two (2) working days of the date of the notification/regret letter, addressed to: The Chairperson, Procurement Committee, Laikipia

Conservancies Association, procurement@laikipiaconservancies.org. Letters or email received after this period shall be treated as null and void.

SECTION III: Tender Evaluation Criteria

After tender opening, tenders will be evaluated in four stages: (1) Preliminary Evaluation, (2) Technical Evaluation, (3) Financial Evaluation, and (4) Due Diligence.

Stage 1: Preliminary Evaluation

Bids will be evaluated based on the criteria below. Bids lacking any of the mandatory documents will be considered non-responsive and eliminated at this stage.

No.	Mandatory Requirement	Marks	Compliant?
1	Copy of Certificate of Incorporation / Registration	1 or 0	
2	Copy of valid KRA Tax Compliance Certificate	1 or 0	
3	Copy of CR12 (or equivalent) generated within the last 12 months	1 or 0	
4	Copy of valid business trading licence	1 or 0	
5	Completed Statement of Financial Capacity, with bank details and a bank reference letter or voided/blank cheque attached	1 or 0	
6	Copies of 2 most recent audited financial statements, signed and dated	1 or 0	
7	Evidence of NCA registration (or equivalent works category) with valid annual practising licence	1 or 0	
8	Commitment to undertake the works across all sites within the proposed schedule	1 or 0	
9	Company profile with details of relevant past experience	1 or 0	
10	All pages sequentially paginated and the document duly signed	1 or 0	

Stage 2: Technical Evaluation

Tenders that pass the Preliminary Evaluation will be scored on the following technical criteria. A bidder must score at least 60% of the total available marks to qualify for Financial Evaluation.

No.	Description of Requirement	Max Score
1	Key personnel: technical team leader and site supervisors — qualifications and years of relevant experience	20 Marks
2	Average annual turnover (last 2 audited financial years) relative to the estimated project cost	15 Marks
3	Proposed methodology and work plan/Gantt chart for sequencing works across all sites	15 Marks
4	Proof of similar completed works within the last 5 years (building construction or rural infrastructure)	20 Marks
5	Equipment and logistical capacity to work across multiple, often remote, sites	15 Marks
6	Health, safety, and environmental management approach	10 Marks
7	Litigation history declaration (sworn affidavit, if any)	5 Marks
	TOTAL	**100 Marks**

Stage 3: Financial Evaluation

Upon completion of Technical Evaluation, a detailed financial evaluation shall follow, comprising three parts:

(a) Determination of Arithmetic Errors — In the event of a discrepancy between the amount in figures and words, the amount in words shall prevail. Where there is a discrepancy between a unit rate and its extended line total, the unit rate as quoted shall prevail unless there is an obvious typographical error.

(b) Comparison of Rates — Items that are significantly under-priced or overpriced may indicate risk of non-delivery or front-loading. Laikipia Conservancies Association may request a detailed cost breakdown for such items before making an award recommendation.

(c) Consistency of Rates — The evaluation committee will compare the consistency of rates for similar items across the Bill of Quantities and note any inconsistencies.

Stage 4: Due Diligence

Laikipia Conservancies Association may subject the top-ranked bidder(s) who pass Technical and Financial Evaluation to a due diligence process, which may include reference checks, site visits to past projects, and verification of submitted documents, prior to final award.

PART B: Financial (Bill of Quantities)

It should be noted that the quantities provided in this Bill of Quantities are approximate and indicative only. The Bidder is required to price each item and indicate the site/facility name on each completed BQ, where more than one copy is required for multiple sites of differing scale.

Bill of Quantities

Bidders are required to complete the Bill of Quantities below in full. Rates and amounts should reflect the cost of drilling, testing, and equipping ONE standard borehole with a solar-powered pumping system to Laikipia Conservancies Association specifications; the Site Schedule and Grand Summary should reflect pricing for the full scope of the borehole in Laikipia. Bidders may attach a separate signed/stamped BQ sheet if more space is required, and should note that drilling rates are typically quoted per meter depth.

Element 1: Siting, Mobilisation and Drilling

Item	Description	Unit	Qty	Unit Rate (KES)	Amount (KES)	Remarks
1	Hydrogeological survey and siting of borehole, including geophysical survey report	Item	1			
2	Mobilisation and demobilisation of drilling rig and equipment to site	Item	1			
3	Drilling of borehole (per metre depth, all strata) — provisional depth pending site survey	LM	150			
4	Geological logging of strata encountered during drilling	Item	1			

Element 2: Casing, Development and Testing

Item	Description	Unit	Qty	Unit Rate (KES)	Amount (KES)	Remarks
1	Supply and installation of uPVC/steel casing (diameter as specified)	LM	150			
2	Supply and installation of screen sections at water-bearing strata	LM	30			
3	Gravel packing around casing/screen annulus	CM	3			
4	Grouting/sanitary seal at surface to prevent contamination ingress	Item	1			
5	Borehole development (airlifting/surging) to remove drilling fluid and fines	Item	1			
6	Test pumping (minimum 24-hour constant/step-rate test) with drawdown and recovery data	Item	1			
7	Water quality testing — physical, chemical, and bacteriological analysis	Item	1			

Element 3: Solar Pumping System

Item	Description	Unit	Qty	Unit Rate (KES)	Amount (KES)	Remarks
1	Supply and installation of solar submersible pump, sized to borehole yield and head	No.	1			
2	Supply and installation of solar photovoltaic panel array, including mounting structure	Item	1			
3	Supply and installation of pump controller and electrical protection devices	Item	1			
4	Rising main, cabling, and associated fittings from pump to wellhead	Item	1			
5	Lightning/surge protection for the solar installation	Item	1			
6	Security fencing/cage around solar panel array to prevent theft and vandalism	Item	1			

Element 4: Storage, Distribution and Wellhead Protection

Item	Description	Unit	Qty	Unit Rate (KES)	Amount (KES)	Remarks
1	Elevated water storage tank (min. 10,000L) on raised steel/masonry stand	No.	1			
2	Pipework from storage tank to domestic draw-off point (tap stand)	LM	50			
3	Domestic tap stand with concrete apron and soakaway/drainage	No.	1			
4	Livestock watering trough with separate supply line and control valve	No.	1			
5	Wellhead protection slab (reinforced concrete) around borehole head	SM	6			
6	Perimeter fencing around borehole, pump house, and storage tank compound	LM	60			
7	Lockable gate/entry point to the compound	No.	1			

Element 5: Community Handover, Labour and Site Reinstatement

Item	Description	Unit	Qty	Unit Rate (KES)	Amount (KES)	Remarks
1	Formation and basic training of community water user committee on operation and maintenance	Item	1			

Item	Description	Unit	Qty	Unit Rate (KES)	Amount (KES)	Remarks
2	Labour — skilled (drilling crew, electrical/solar technician, masons)	Item	1			
3	Labour — unskilled (general site assistance)	Item	1			
4	Site reinstatement and clean-up on completion	Item	1			
5	Handover documentation, drilling/test-pumping logs, and photographic record per site	Item	1			
6	Other (specify)	Item	1			
	Subtotal (per borehole)					
	Contingency (%)					
	VAT / Applicable Taxes					
	TOTAL COST PER BOREHOLE (KES)					

Site Schedule and Summary

The unit cost per borehole established in the Bill of Quantities above shall be applied to the site listed below, adjusted for actual drilled depth, unless site-specific ground conditions are flagged.

Site No.	Borehole / Location	County	Depth (m)	Cost (KES)
1				
2				
	SUBTOTAL — ALL SITES			

Grand Summary — Full Scope of Works

Item	Description	No. of Borehole	Total Amount (KES)
1	Subtotal — all sites (from Site Schedule above)		
2	Mobilisation / demobilisation costs (if quoted separately)		
3	Supervision / project management costs (if quoted separately)		
	GRAND TOTAL (KES) — Inclusive of All Taxes		

(Carried to Form of Tender)

Bidder Name: _____

Authorised Signature: _____ Date: _____

Company Stamp/Seal: